INSTALLATION INSTRUCTIONS EWC-7-11-**P, EWC-7-12-**P MAGIC-PAK CHASSIS FOR R-410A CABINETS

This manual must be left with the homeowner for future reference.

This manual is for the replacement of EXISTING R-410A cabinet with a R-454B chassis. Reference the rating plate of the equipment being replaced. If the rating plate states R-410A, please proceed forward. If the rating plate states R-454B, please follow the included Installation Manual 508684-01

This is a safety alert symbol and should never be ignored. When you see this symbol on labels or in manuals, be alert to the potential for personal injury or death.

A WARNING

This chassis shall be installed by a qualified agency in accordance with the manufacturer's instructions and all applicable codes and requirements of the authority having jurisdiction. If the information in these instructions is not followed exactly, electric shock, fire, or explosion may result, which may cause property damage, personal injury, or death. The qualified service agency performing this work assumes responsibility for properly installing this chassis.

A WARNING

This Chassis is designed for, and should only be used in, Magic-Pak® EWC models of similar cooling capacity. Any other use could result in actions that might cause property damage, personal injury, or death

A WARNING

Consult current EWC specifications to ensure wire and breaker are sized appropriately.

Manufactured By Allied Air Enterprises LLC 215 Metropolitan Drive West Columbia, SC 29170



A WARNING

Risk of electrical shock. Disconnect all remote power supplies before installing or servicing any portion of the system. Failure to disconnect power supplies can result in property damage, personal injury, or death.

Parts List

Quantity	Part						
1	Safety Label 107891-01						
1	Safety Label 107894-01						
1	Safety Label 107659-01						
1	Safety Label 107660-01						
1	Safety Label 107661-01						
1	Safety Label 108173-01						
1	Low Voltage Adapter Harness (104495-06)						
1	Heater Jumper Harness (104495-07)						
1	Wiring Diagram Label						
1	2.5 Ton 2-Stage Adapter (104495-10)						
1	2.5 Ton 2-Stage Adapter (104495-11)						
1	Installation Instructions						



A WARNING

Auxiliary devices which may be a potential ignition source shall not be installed in the duct work. Examples of such potential ignition sources are hot surfaces with a temperature exceeding 1,292 F (700°C) and electric switching devices.

A WARNING

For appliances using A2L refrigerants connected via an air duct system to one or more rooms, only auxiliary devices approved by the appliance manufacturer or declared suitable with the refrigerant shall be installed in connecting ductwork.

A WARNING

- Do not use means to accelerate the defrosting process or to clean, other than those recommended by the manufacturer.
- The appliance shall be stored in a room without continuously operating ignition sources (for example: open flames, an operating gas appliance, or an operating electric heater).
- Do not pierce or burn.
- Be aware that refrigerants may not contain an odor.

A WARNING

Any service personnel installing, decommissioning, or performing maintenance on the unit must be properly trained with A2L refrigerants.

A WARNING

For duct connected appliances, false ceilings or drop ceilings may be used as a return air plenum if a REFRIGERANT DETECTION SYSTEM is provided in the appliance and any external connections are also provided with a sensor immediately below the return air plenum duct joint.

A WARNING

If this appliance is conditioning a space with an area smaller than TA_{min} or stored in a space with an area smaller than A_{min} as defined by this instruction, then that space must be without continuously operating open flames (e.g. an operating gas appliance) or other potential ignition sources (e.g. an operating electric heater or similar hot surface). A flame-producing device may be installed in the same space if the device is provided with an effective flame arrest system.

NOTE – R454B is an A2L refrigerant. The system installation must meet the following parameters based upon total refrigerant charge (line set included). TAmin (Total minimum conditioned area) is the minimum allowable conditioned area based upon the total system charge at sea level. Values must be multiplied by altitude adjustment factor at installed altitude.

See tables below

TAmin Table								
Charge (lb)	<4	4	6	8	10			
Charge (kg)	<1.8	1.8	2.7	3.6	4.5			
Minimum Conditioned Area (ft2)	N/A*	60	90	120	150			
Minimum Conditioned Area (m2)	N/A*	5.6	8.4	11.2	14.0			

NOTE – Multiply values in TAmin table by the Altitude Adjustment Factors to correct TAmin based on installed altitude.

Altitude (m)	0	200	400	600	800	1000	1200	1400	1600
Altitude (ft)	0	660	1310	1970	2620	3280	3940	4590	5250
Adj. Factor	1	1	1	1	1.02	1.05	1.04	1.1	1.12
Altitude (m)	1600	1800	2000	2200	2400	2600	2800	3000	3200
Altitude (ft)	5250	5910	6560	7220	7870	8530	9190	9840	10500
Adj. Factor	1.12	1.15	1.18	1.21	1.25	1.28	1.32	1.36	1.4

IMPORTANT

A WARNING

For duct connected appliances, false ceilings or drop ceilings may be used as a return air plenum if a REFRIGERANT DETECTION SYSTEM is provided in the appliance and any external connections are also provided with a sensor immediately below the return air plenum duct joint.

To install this chassis into a R-410A cabinet, the installer will be required to have a video conference with an agency representative to validate the installation and that all proper safety precautions have been followed. There will be some questions that will be asked and required to be answered before a video chat will occur for validation. This validation process will occur after the installation of the chassis, but prior to unit startup. This installation must be verified upon completion of the replacement by following the Magic-Pak Chassis Retrofit Virtual Validation instructions at the end of this manual. Failure to follow this installation manual in its entirety will void all warranty claims with the unit.

The installer will be required to provide the following information:

- Installation address
- Serial number of the new chassis
- Serial number of the cabinet
- If the system is ducted (Note: the unit must be ducted to replace the chassis.).
- If an optional refrigerant detection system in installed.

- If the system is installed in a free air return application (Note: RDS systems are required for free air return applications).

- The installer will need to be able to show the markings on the unit, and the connection points of the installed chassis.

• Work shall be undertaken under a controlled procedure so as to minimize the risk of a flammable gas or vapor being present while the work is being performed.

• The area shall be checked with an appropriate refrigerant detector prior to and during work, to ensure the technician is aware of potentially toxic or flammable atmospheres.

• Ensure that the detection equipment being used is suitable for use with all applicable refrigerants, i. e.n non-sparking, adequately sealed or intrinsically safe.

• If any hot work is to be conducted on the refrigerating equipment or any associated parts, the appropriate fire extinguishing equipment shall be available to hand.

• Have a dry powder or CO2 fire extinguisher adjacent to the charging area.

• No person carrying out work in relation to a refrigerating system which involves exposing any pipe work shall use any sources of ignition in such a manner that it may lead to the risk of fire or explosion. All possible ignition sources, including cigarette smoking, should be kept sufficiently far away from the site of installation, repairing, removing and disposal, during which refrigerant can possibly be released to the surrounding space. Prior to work taking place, the area around the equipment is to be surveyed to make sure that there are no flammable hazards or ignition risks. "No Smoking" signs shall be displayed.

• Ensure that the area is in the open or that it is adequately ventilated before breaking into the system or conducting any hot work. A degree of ventilation shall continue during the period that the work is carried out.

• Pipe-work including piping material, pipe routing, and installation shall include protection from physical damage in operation and service, and be in compliance with national and local codes and standards

• All field joints shall be accessible for inspection prior tbeing covered or enclosed

• Where electrical components are being changed, they shall be fit for the purpose and to the correct specification. At all times the manufacturer's maintenance and service guidelines shall be followed. If in doubt, consult the manufacturer's technical department for assistance. The following checks shall be applied to installations using FLAMMABLE REFRIGERANTS as applicable:

1. The actual refrigerant charge is in accordance with the room size within which the refrigerant containing parts are

4. Markings on the equipment should be visible and legible. Markings and signs that are illegible shall be corrected.

5. Refrigerating pipe or components are installed in a position where they are unlikely to be exposed to any substance which may corrode refrigerant containing components, unless the components are constructed of materials which are inherently resistant to being corroded or are suitably protected against being so corroded.

· For systems containing refrigerant, all repair and maintenance to electrical components shall include initial safety checks and component inspection procedures such as that capacitors are discharged in a safe manner to avoid possibility of sparking, that no live electrical components and wiring are exposed while charging, recovering, or purging the system, and that there is continuity of earth bonding. If a fault exists that could compromise safety, then no electrical supply shall be connected to the circuit until it is satisfactorily dealt with. If the fault cannot be corrected immediately but it is necessary to continue operation, an adequate temporary solution shall be used that is reported to the owner of the equipment, so all parties are advised.

NOTE –Sealed electrical components shall be replaced, not repaired.

NOTE – Intrinsically safe components must be replaced, not repaired.

NOTE – All maintenance staff and others working in the local area shall be instructed on the nature of work being carried out with work in confined spaces being avoided.

· Under no circumstances shall potential sources of ignition be used in the searching for or detection of refrigerant. A halide torch (or any other detector using a naked flame) shall not be used. The following detection methods are deemed acceptable for all refrigerant systems. Electronic detectors may be used to detect refrigerant, but in the case of flammable refrigerants, the sensitivity may not be adequate, or may need re-calibration. (Detection equipment shall be calibrated in a refrigerant-free area.) Ensure that the detector is not a potential source of ignition and is suitable for the refrigerant used. Detection equipment shall be set at a percentage of the LFL of the refrigerant and shall be calibrated to the refrigerant employed, and that 12.5 % refrigerant is confirmed. Detection fluids are also suitable for use with most refrigerants but the use of detergents containing chlorine shall be avoided as the chlorine may react with the refrigerant and corrode the copper pipe-work. In the event refrigerant is detected by sensor, all naked flames shall be removed/ extinguished. If refrigerant is found which requires brazing, all of the refrigerant shall be recovered from the system, or isolated (by means of

 When breaking into the refrigerant circuit to make repairs - or to any other purpose - conventional procedures shall be used. However, for flammable refrigerants it is important that best practice be followed and, since flammability is a consideration, procedures such as safely removing refrigerant following local and national regulations, purging the circuit with inert gas (optional for A2L), evacuating (optional for A2L), or opening the circuit by cutting or brazing be adhered to. The refrigerant charge shall be recovered into the correct recovery cylinders if venting is not allowed by local and national codes. For appliances containing flammable refrigerants, the system shall be purged with oxygen-free nitrogen to render the appliance safe for flammable refrigerants. This process might need to be repeated several times. Compressed air or oxygen shall not be used for purging refrigerant systems. For appliances containing flammable refrigerants, refrigerants purging shall be achieved by breaking the vacuum in the system with oxygenfree nitrogen and continuing to fill until the working pressure is achieved, then venting to atmosphere, and finally pulling down to a vacuum (optional for A2L). This process shall be repeated until no refrigerant is within the system (optional for A2L). When the final oxygen-free nitrogen charge is used, the system shall be vented down to atmospheric pressure to be able to perform the required work. Ensure that the outlet for the vacuum pump is not close to any potential ignition sources and working area is well ventilated.

General Instructions

This chassis is the self-contained cooling section of an EWC unit. It is designed to be assembled into an EWC cabinet, and is not intended for any other use or application.

This chassis is compatible with the following legacy models: **EWC4-09-121, **EWC4-09-181, **EWC4-09-241, **EWC4-09-301, EWC**09P30, EWC**11P12, EWC**11P18, EWC**11P24, EWC**12P**, and EWC**13P**

If any damage to the contents is found at the time of delivery, proper notation should be made on the carrier's freight bill. Damage claims should be filed with the carrier at once. Claims of shortage should be filed with the manufacturer within 5 days.

Removing the Old Chassis

- 1. Make sure that the electrical supply is disconnected.
- 2. Remove the filter access panel and center rear panel.
- 3. Disconnect the wire harness plug and remove the line voltage wires from the contactor.
- 4. Disconnect the condensate drain tube from drain pan.
- 5. Remove the blower close-off panel and remaining screws retaining the chassis in the cabinet.
- 6. Slide out the existing chassis.



7. Remove the (2) right most screws behind the chassis stop bracket on the underside of the control panel.



Install the deflector bracket into the cabinet using the (2) screws removed during the previous step.



- 9. Slide in new EWC chassis and attach chassis in reverse order of the removal.
- 10. Attach black line voltage wires to L1 and L2 of contactor.



- a. For **EWC4-09-301: Attach 6-pin plug of chassis to 104495-10, and attach 104495-10 to 6-pin plug of cabinet.
- b. b. For EWC**09P30 and EWC**12P30: Attach 6-pin plug of chassis to 104495-11, and attach 104495-11 to 6-pin plug of cabinet.
- c. c. For all **EWC4-09-121, **EWC4-09-181, **EWC4-09-241: Attach 6-pin plug of chassis to 104495-06, and attach 104495-16 to 6-pin plug of cabinet.
- d. d. For all other models: Attach 6-pin plug of chassis to 6-pin plug of cabinet.

Page 6 of 16



NOTE: NOTE: For EWC**09P30, EWC**11P12, EWC**11P18, EWC**11P24, EWC**12P**, or EWC**12P** series units, skip to step 15. Proceed for all other legacy models

- 11. Remove upper panels to access heating element compartment.
- 12. Remove white "W" wire coming from thermostat to heater element.



13. Attach female terminal of 104495-07 adapter to the location where the "W" wire was routed. Attach the removed wire to the male terminal on the white wire of the 104495-07 adapter.



14. Remove both black wires coming from the plug on the unit going to either the auxiliary relay or heater sequencer (depending on model). Attach both black wires to the remaining terminals in the 104495-07 adapter.



- 15. Re-install the center rear panel on the unit, being careful not to pinch any wiring.
- 16. Re-install the filter access panel on the center rear panel.
- 17. Establish the electrical supply to the unit and check the following.
 - e. Set thermostat for a call for cooling.
 - f. The compressor, condenser fan, and blower will start approximately 8 seconds after the thermostat calls for cooling.
 - g. When the thermostat is satisfied in the cooling mode, the compressor and condenser fan motor will shut off immediately. The circulating air blower will continue to operate for approximately 90 seconds.

- h. Set the thermostat to call for heat.
- i. Verify heat elements operate.
- j. Allow the unit to reach steady state conditions and verify that the unit is operating at the desired outlet temperature.
- k. Turn thermostat down. The circulating air blower will continue to operate for approximately 30 seconds after the thermostat is satisfied.
- 18. Install the new wiring diagram (supplied) on the unit over the existing wiring diagram. If wire modifications were required, mark the changes on the wiring diagram for future reference.

- 19. Find the appropriate labels as shown below that were supplied with the replacement chassis:
 - I. 107893-01
 - m. 107894-01
 - n. 107659-01
 - o. 107660-01
 - p. 107661-01
 - q. 108173-02
- 20. Place the safety labels onto the exterior chassis viewable when facing the unit as shown in the diagram below.



21. Install the new rating plate labels over the existing rating plate to update the refrigerant information on the rating plate. The rating plate will be replaced in the sections shown below in orange.

1	EWC1512	P2481		SER. NO.	1623M02787	
i	ELECTRICAL	DATA	MIN VOLTAGE		IN DADUT	1
	¥0,15 /	N HZ	8 60 142		ANTROIT	
	(208) 238	1~60	187	CX CX	11(25)28.4 12(43.3)58.0	
	DHORT CIR	OULT CURREN	AT S &A AMS STO	METR	CAL, SEE & MAXIMUM	
		COMPRE LISO	R BLOWER MTR	004	CONSERVAN MTR	
	RA	18.2				
	PHADE	1	1		1	
	FLA	-	27		13	
	MAX FUSE FOR OVER CTKT (30	DR DIRCUIT DURRENT PR	BREAKER (HACR) DTECTION : CKT2 (45 350	PER NO	D	
	HEATER ANPE		MAX OUTLET AUR TEMP		STATIC PRESSURE	
	CKT1 (15 CKT2 (34	2125	200 ° F		65 IK. H.C.	
	CONTAINS	8-4548	MAX A	CLOWA	ALL PRODUCTS	-
	PACTORY	CHARGE / L ST ATLAN	NI SIDE	100	THE POLY (1977 MAR)	-
	3100 9103	f raing	MAXIMU	M ALL	WARLE PRESSURE	
	PLENUM 1 Maximum coli	DUCT	AANCES CABINET 1	artov	when tested to	
	CONFORMS TO CONFORMS TO CSA 22.2 6033	153 (correct 0 UL STO 60 15-1 & 603	1035 - 1 & 60335 1035 - 2 - 40	-2-1	IO CERTIFIED TO	
c .i) us ek	C C C C C C C C C C C C C C C C C C C	R1	CERTIFIEI The second s	D
4	20	i	MANUFACTURE	D 87	iE.	_
		-	NUMBER OF			

22. Proceed to the MagicPak Chassis Retrofit Virtual Validation Instructions on the next page.

Magic Pak Chassis Retrofit Virtual Validation Instructions

- 1. Once all previous steps have been completed, please call the ETL validation hot-line to certify the unit safe for use at 1-212-803-5322
- 2. When the validator answers please advise them that you are calling to: "Validate a Magic Pak Chassis Retrofit"
- 3. The validator will then ask for your name, phone number and email address
- 4. The validator will then confirm some information on the unit such as:
 - Installation Address
 - Serial Number of the Existing cabinet
 - · Serial Number of the REPLACEMENT chassis
 - Validate that the unit is compatible for conversion. ONLY R-410A units are eligible for conversion.
- 5. The validator will ask if the field wiring and overcurrent protection or breaker size has been checked to be compliant with the updated electrical specifications? (yes or no) What is the current wire gauge size? (xx gauge) What is the breaker size installed? (xx Amps) A response of no will require the field wiring and overcurrent protection devices be updated before validation can be completed.
- 6. The validator will ask if the refrigerant deflector was installed per steps 7-9 in the installation manual? (yes or no). An answer of no will require the installer to remove the chassis and install the supplied refrigerant deflector to the cabinet of the unit (steps 7-9 in the installation manual above). The validator will then ask the question: Is the unit a free air return application? (yes or no)
- 7. The validator will then ask the question: Is the unit a free air return application? (yes or no)
- 8a. If response to question 7 is yes, a field installed RDS is required and the validator will then ask the question: Is the field installed RDS kit installed? (yes/no) An answer of no will require the installer to install and test the RDS system before calling back to certify.
- 8b. If the answer to question 7 is no, the validator will ask: is the optional RDS kit installed? (yes/no). It is ok to proceed to a teams call with an answer of no in this situation. No validation of RDS installation is required.
- 9. If the answer to either 8a or 8b was yes, the validator will ask: Has the test procedure been conducted on the RDS kit and verified? An answer of no will prompt the validator to ask that the installer perform the test procedure on the RDS system before calling back to certify.

1. The validator will then send you a TEAMS invite via email to you that you would need to accept and join. You would stay on the original phone conversation but initiate a video share on your end to allow the validator to capture the following images:

• Picture of the newly placed cooling section label overtop of existing Nameplate of Magic Pak Unit. This will allow Intertek Rep to confirm the Serial Number as well as confirmation of newly placed label.

• Example:

SER. 1623M02787 EWC1512P24B1B MODEL & SERIAL NO. REQUIRED TO REQUEST SERVICE. MFG:08/2024 MIN VOLTAGE ELECTRICAL DATA MIN CIRCUIT
 WOLTS
 PH
 HZ
 ® 60 HZ

 (208) 230
 1
 60
 197
CKT1 (25) 28.4 CKT2 (43.3) 50.0 SHORT CIRCUIT CURRENT: 5 KA RMS SYMMETRICAL, 600 V MAXIMUM COMPRESSOR BLOWER MTR CONDENSER FAN MTR 10.2 61.6 1 LRA PHASE MAX FUSE OR CIRCUIT BREAKER (HACR PER NEC) FOR OVER CURRENT PROTECTION : CTKT (30)30 AMPS CKT2 (45)50 AMPS HEATER MAX OUTLET AMPS AIR TEMP MAXIMUM EXTERNAL STATIC PRESSURE CKT1 (15.2) 17.5 CKT2 (34.7)40.0 200° F 0.5 IN. W.C. MAX ALLOWABLE PRESSURE HI SIDE LOW SIDE CONTAINS R-4548 FACTORY CHARGE 3 LBS 8 0ZS (1.61 kg) 446 PSIG (3075 kPA) 236 PSIG (1627 kPA) MAXIMUM ALLOWABLE PRESSURE 640 PSIG (4412.8 kPA) MINIMUM CLEARANCES PLENUM DUCT CABINET ximum cabinet leakage 1.4% of rated airflow when tested to SUASHRAE 193 (complies with IECC 2015) IS TO UL STD 60335-1 & 60335-2-40 CERTIFIED TO 60335-1 & 60335-2-40 ALR CERTIFIED. Unitary Small AC AHRI Standard 210/240 erblication applies Intertek IPX4 ANUFACTURED BY ALLIED AIR ENTERPRISES, LLC. WEST COLUMBIA, SC 29170

EWC*** Example



HWC*** Example

- Picture of the New Marking Labels on the Outside of the MagicPak Unit
 - Example:



Desired Location of Safety labels

Required Safety Labels for the Outside of the Magic Pak Unit

ETIPR	Charge (lb)	<4	4	6	8	10	
108173-02	Charge (kg)	<4	1.8	2.7	3.6	4.5	
Minimum Conditione	N/A**	60	90	120	150		
Minimum Conditione	ed Area (m²)	N/A**	5.6	8.4	11.2	14.0	
* Units with refrigerant charge below 4 lb, (1.8 kg) do not require a minimum conditioned room area.							





- Picture of the two connection points to ensure secure installation:
 - o Example:



- Picture of the wire size and overcurrent protection.
 - o Example:



Picture of the field wiring to unit (Picture should clearly show wire gauge)

Picture of overcurrent protection (Picture should clearly show breaker size)

 Picture of the RDS Sensor and Board Installation (if applicable) o Example:



RDS Mitigation Board



RDS Sensor Installation